

### **DeKalb County Zoning Board of Appeals**

Department of Planning & Sustainability 178 Sams Street, Decatur, GA 30030 DeKalb Planning

Lorraine Cochran-Johnson

Wednesday, December 10, 2025

**Planning Department Staff Analysis** 

Interim Director

Juliana Njoku

Chief Executive Officer

N16. Case No: A-26-1247790

Parcel ID(s): 18 047 23 029

#### **Commission District 04 Super District 06**

**Applicant:** Caren Ann Nunnally and Nealon Hightower

P.O. Box 330

Avondale Estates, GA 30002

Owner: Scottdale 30 LLC

2221D Peachtree Road

Suite #220

Atlanta, GA 30309

**Project Name:** 436 Booker Avenue – Residential Construction

**Location:** 436 Booker Avenue, Scottdale, GA 30079

**Request(s):** Application by Caren Ann Nunnally and Nealon Hightower to request variances from:

- 1. Section 27-3.36.10. (1) to: reduce the required front yard setback from 30 feet to 15 feet and reduce the required rear yard setback from 30 feet to 18 feet.
- 2. Section 27-3.36.10. (5)(c)(1) to increase the maximum lot coverage from 35 percent to 38.1 Percent.
- 3. Section 27-3.36.12. to waive the sidewalk requirement.

Staff Recommendation: Approval with conditions

#### Conditions:

1. The following information about this variance shall be noted on any site plan prepared for the subject property: case number, approval date, type of variance and condition(s) of approval.

#### **STAFF FINDINGS:**

The applicants, Caren Ann Nunnally and Nealon Hightower, request the above-referenced variances from the DeKalb County *Zoning Ordinance* in order to construct a new single-family detached dwelling.

The subject property is located in an R-75 (Residential Medium Lot-75) Zoning District and is also located within Tier 2 of the Scottdale Overlay District, which supersedes most developmental standards of the R-75 Zoning District such as permitted uses, setbacks, lot coverage, etc. The property is nonconforming with respect to lot area (approximately 2,798 square feet versus 5,000 square feet required) but is a legal lot of record. The legal status of this nonconforming lot permits a new single-family detached dwelling to be constructed per Section 27-8.1.3. of the *Zoning Ordinance*, provided that development standards are met or variances are obtained to seek relief from these standards.

1. There is an extraordinary or exceptional physical condition(s) pertaining to the particular piece of property (such as, but not limited to, lot size, lot shape, specimen tree(s), steep slope(s), or preservation of historic characteristics of the property), which was not created by the current owner, previous owner, or applicant; by reason of a clearly demonstrable condition(s), the strict application of the requirements of this chapter would deprive the property owner of rights and privileges enjoyed by other property owners in the same zoning district, as distinguished from a special privilege or convenience sought by the property owner.

The subject property is approximately 55-56 feet deep, which prevents strict adherence to current developmental standards. These conditions were not created by the property owner, and a strict denial of the variance requests would likely deprive the property owner of any viable economic use of the property. Other properties along Booker Avenue and Proctor Avenue share the same or have similar size restrictions. The property also contains steep slopes that may make the installation of a sidewalk (as required by Section 27-3.36.12.) impractical.

2. The requested variance does not go beyond the minimum necessary to afford relief, and does not constitute a grant of special privilege inconsistent with the limitations upon other properties in the zoning district in which the subject property is located:

The requested variances do not appear to go beyond the minimum relief necessary in order to construct a single-family detached dwelling on the subject property, but instead represent a balance in terms of building size/placement. The proposal is consistent with the requests for variances for other properties in the vicinity, which, as previously stated, share the same or have similar size restrictions as the subject property.

3. The grant of the variance will not be materially detrimental to the public welfare or injurious to the property or improvements in the zoning district in which the subject property is located:

The requested variances will not be detrimental to the public welfare or injurious to nearby properties. The request to eliminate the sidewalk along the property's frontage is offset by the opportunity for a continuous sidewalk network along the eastern side of Booker Avenue – which is relatively flat and has sufficient Right-of-Way (ROW) to accommodate said sidewalk without any potential dedication being required.

4. The literal interpretation and strict application of the applicable provisions or requirements of this chapter would cause undue and unnecessary hardship:

Adherence to current setback requirements would result in the subject property having no building envelope. Topography appears to prevent a sidewalk from being installed along the property's frontage to the full extent required. The literal interpretation and strict application of the *Zoning Ordinance* would ultimately deprive the property owner of a viable economic use of the property.

### 5. The requested variance would be consistent with the spirit and purpose of this Chapter and the DeKalb County Comprehensive Plan Text:

The subject property is located within a Traditional Neighborhood (TN) Character Area, per the *DeKalb County 2050 Unified Plan.* Traditional Neighborhoods typically have "...small, regular lots, and buildings closer to the front property line" (*Dekalb County 2050 Unified Plan*, pg. 38). Traditional Neighborhoods also encourage "innovative housing types to increase housing choice, income diversity, and limited neighborhood density" (pg. 39). Approval of the requested variances would allow for a dwelling that appears to align with the Traditional Neighborhood's goals and intent.

#### FINAL STAFF ANALYSIS:

Staff believes that the variance requests represent a balanced proposal to allow for a single-family detached dwelling that meets the goals and intent of the *DeKalb County 2050 Unified Plan* and the *Zoning Ordinance*. The property's shallow depth restricts its buildability without the provision of variances. All five (5) hardship criteria appear to be met. Therefore, the Planning and Sustainability Department recommends *Approval with Conditions* of this Variance application.

Staff Recommendation: Approval with conditions

#### Conditions:

1. The following information about this variance shall be noted on any site plan prepared for the subject property: case number, approval date, type of variance and condition(s) of approval.



Development Services Center 178 Sams Street Decatur, GA 30030

www.dekaibcountyga.gov/planning 404-371-2155 (o); 404-371-4556 (f)

Chief Executive Officer Michael Thurmond

### DEPARTMENT OF PLANNING & SUSTAINABILITY

Interim Director Cedric Hudson

# ZONING BOARD OF APPEALS APPLICATION FOR PUBLIC HEARING (VARIANCES, SPECIAL EXCEPTIONS, APPEALS OF ADMINISTRATIVE DECISIONS)

Applicant and/or Authorized Representative: Caven Ann Numary / Newton Hightower
Mailing Address: PO Box 330
City/State/Zip Code: AVONCIALLE ESTATS, GA 30002
Email: C2 Expectiting@upinoo.com/nealnightower@gmail.com
Telephone Home: 404) 441-5355 Business: 404) 441-5355
OWNER OF RECORD OF SUBJECT PROPERTY
owner: Switchele 30 LCC
Address (Mailing): 2221 D Peachtree. Rd # 220
Email: JWMANSHAM@gmail.Com Telephone Home: 404-672-1031 Business: 404-672-1031
ADDRESS/LOCATION OF SUBJECT PROPERTY
Address: 434 Booker Ave city: Sittlede state CA zip: 30079
District(s): 18 Land Lot(s): 047 Block: 23 Parcel: 029
Zoning Classification: Suttinic Tier 2 Commission District & Super District: 43 C
CHECK TYPE OF HEARING REQUESTED:
VARIANCE (From Development Standards causing undue hardship upon owners of property.)
SPECIAL EXCEPTIONS (To reduce or waive off-street parking or loading space requirements.)
OFFICIAL APPEAL OF ADMINISTRATIVE DECISIONS.

\*PLEASE REVIEW THE FILING GUIDELINES ON PAGE 4. FAILURE TO FOLLOW GUIDELINES MAY RESULT IN SCHEDULING DELAYS.\*

Email plansustain@dekalbcountyga.gov with any questions.

#### **LETTER OF INTENT**

Dear Members of the Zoning Board of Appeals,

I am writing to request variances for property located at 436 Booker Ave, Scottdale GA 30079, from **Section 27-3.36.10 of the DeKalb County Zoning Ordinance** as it applies to the Scottdale Tier Two Overlay District. The subject property is a **confirmed legal lot of record**. It is unusually small, specifically shallow, compared to most of the other small lots in the neighborhood. We seek relief from the code to construct a small 2 bedroom, 1 bath, house that is similar in nature to the original homes in the neighborhood 100 years ago.

Specifically, we seek relief from requirements related to:

- Reduce front setback from 30 feet to 10 feet
- Reduce rear setback from 30 feet to 15 feet
- Increase maximum lot coverage from 35% to 39.1%
- Reduce landscape strip from 5 feet to 1 foot
- Reduce sidewalk to curb from 4 feet to 1 foot
- Reduce minimum parking space size to 86 square feet

Due to the lots' size, configuration, and overlay restrictions, strict compliance with these requirements would make development impossible.

#### 1. Physical Conditions of the Site

The lot is exceptionally small, only 55 feet deep compared to standard R-75 parcels that are over 200 feet deep. Its dimensions were established long before the adoption of the Scottdale Tier Two overlay requirements. These conditions are inherent to the properties and were not created by the applicant. Strict compliance with current standards for coverage, setbacks, sidewalks, parking space size, landscaping strips is physically impossible due to these unique lot conditions. We have already shrunk the house below standards just to achieve these reduced requests.

#### 2. Minimum Variance Necessary

The relief requested is the minimum necessary to allow reasonable use of the property. Relief from sidewalk and landscape strip requirements and coverage is necessary because of the physical constraints and limited front-yard area, but we will maintain a safe and attractive frontage and we have managed to follow all of the remaining hundreds of requirements of R-75 and Tier Two. Each variance request has been tailored to achieve only what is essential for development, without granting any special advantage inconsistent with other properties.

#### 3. Public Welfare

The proposed home will not be detrimental to public welfare or injurious to neighboring properties. On the contrary, it will provide high-quality, affordable housing in an area where housing diversity is *desperately* needed. We anticipate offering this home at less than 1/3 the cost of new construction in the neighborhood. The smaller scale is consistent with the Traditional Neighborhoods Character Area in the Comprehensive Plan, which encourages walkability with very close proximity to The Path and public transportation. We are only asking to reduce sidewalk and landscape strip requirements, not remove them. This will in no way diminish the neighborhood character but will instead make development feasible and weave into the fabric of the community unlike anything Scottdale has seen in over 100 years. Our mission is to provide the people with new housing options they can actually afford, a welcomed alternative from the million dollar new construction options which are currently being built in Scottdale. This is only possible with your help and the requested relief.

#### 4. Ordinance Hardship

A literal interpretation of Section 27-3.36.10 would prohibit any reasonable development of these lots, effectively rendering them unusable as they have sat from the time they were platted until present day. Codes and requirements have only become more constrictive to smaller homes over the years. Without relief, the lot would remain vacant and unproductive. This constitutes an undue and unnecessary hardship that was not self-created, as the lot sizes, shapes, and separation predate the current ordinance. A considerable part of our hardship is the new legal requirement by DeKalb County to deed away the first five feet of our property to the County for sidewalks. With those constraints our houses are pushed back another 5 feet, we have less land to meet coverage requirements and parking becomes even more difficult on an already tight non conforming lot. We asked County officials if we could waive that requirement and ask for less variances and they were insistent that that land be given to the County free of charge and told us to ask for variances and list that as a hardship.

#### 5. Alignment with the Spirit of the Law & Comprehensive Plan Findings

The requested variances are consistent with the spirit and intent of the DeKalb County Zoning Ordinance and the **DeKalb 2050 Comprehensive Land Use Plan**. Specifically:

- Housing Diversity and Affordability: The Plan identifies the need for smaller, more affordable housing options to meet the needs of a broad range of residents. These homes directly advance that goal.
- Traditional Neighborhood Character: The Plan highlights the importance of walkable, traditional neighborhoods with smaller lots and houses closer to the street. The proposed variances allow us to maintain this character while adapting older lots for modern use.
- **Infill Development**: The Plan encourages efficient use of land through infill development on existing lots of record. Our proposal reactivates underutilized parcels without requiring new infrastructure.

• **Sustainability and Transportation**: By providing a modest-sized home, the project supports compact development patterns and aligns with County goals to reduce sprawl and encourage transit and pedestrian use.

#### Conclusion

We believe that people should not be forced to live outside of our community due to unaffordability and they should be given the opportunity to own their little slice of the American Dream. For the reasons stated above, we respectfully request that the Board grant the requested variances from Section 27-3.36.10. We have met with DeKalb County planning officials on multiple occasions to thoughtfully craft the most ideal scenario that would most adhere to codes and achieve feasibility. The proposed relief represents the minimum deviation necessary to enable development of this unusually small lot, while protecting public welfare, furthering the goals of the Comprehensive Plan, and providing much-needed affordable housing in Scottdale. Approvals such as these by this Commission would free up many un-buildable lots in Scottdale and allow the County to fully utilize the land we have available.

Thank you for your time and thoughtful consideration.

Respectfully,

**Neal Hightower** 



#### **ZONING BOARD OF APPEALS APPLICATION**

#### **AUTHORIZATION TO REPRESENT THE PROPERTY OWNER**

I hereby authorize the staff and members of the Zoning Board of Appeals to inspect the premises of the Subject Property

I hereby certify that the information provided in the application is true and correct.

I hereby certify that I am the owner of the property and that I authorize the applicant/agent to apply for a hearing to the ZoningBoard of Appeals for the requests as shown in this application.

DATE: 9-25-25 Applicant/Agent: Signature	Allower Mar Sustan But
TO WHOM IT MAY CONCERN:	
(I)/ (WE)	
being (owner/owners) of the property describe to the low of attached to the property describe to the low of attached to the low of the property describe to the low of attached to the low of the property describe to the low of the l	hereby delegate authority to:  Owner  Owner
Notary Public	Owner
Notary Public	Owner





# ZONING BOARD OF APPEALS APPLICATION AUTHORIZATION OF THE PROPERTY OWNER

I hereby authorize the staff and members of the Zoning Board of Appeals
To inspect the premises of the Subject Property

I hereby certify that the information provided in the application is true and correct.

I hereby certify that I am the owner of the property subject to the application.

DATE: <u>9-25-25</u>	Applicant: All Ince Signature
DATE:	Applicant:Signature

#### LETTER OF INTENT

Dear Members of the Zoning Board of Appeals,

I am writing to request variances for property located at 436 Booker Ave, Scottdale GA 30079, from **Section 27-3.36.10 of the DeKalb County Zoning Ordinance** as it applies to the Scottdale Tier Two Overlay District. The subject property is a **confirmed legal lot of record**. It is unusually small, specifically shallow, compared to most of the other small lots in the neighborhood. We seek relief from the code to construct a small 2 bedroom, 1 bath, 776 SF house that is similar in nature to the original homes in the neighborhood 100 years ago.

Specifically, we seek relief from requirements related to:

- Reduce front setback from 30 feet to 15 feet
- Reduce rear setback from 30 feet to 18 feet
- Increase maximum lot coverage from 35% to 38.1%
- Waive sidewalk requirements

Due to the lots' size, configuration, and overlay restrictions, strict compliance with these requirements would make development impossible.

#### 1. Physical Conditions of the Site

The lot is exceptionally small, only 55 feet deep compared to standard R-75 parcels that are over 200 feet deep. Its dimensions were established long before the adoption of the Scottdale Tier Two overlay requirements. These conditions are inherent to the properties and were not created by the applicant. Strict compliance with current standards for setbacks, sidewalks is physically impossible due to these unique lot conditions. We have already shrunk the house below standards just to achieve these reduced requests.

#### 2. Minimum Variance Necessary

The relief requested is the minimum necessary to allow reasonable use of the property. Relief from sidewalk and landscape strip requirements and coverage is necessary because of the physical constraints and limited front-yard area, but we will maintain a safe and attractive frontage and we have managed to follow all of the remaining hundreds of requirements of R-75 and Tier Two. Each variance request has been tailored to achieve only what is essential for development, without granting any special advantage inconsistent with other properties.

#### 3. Public Welfare

The proposed home will not be detrimental to public welfare or injurious to neighboring properties. On the contrary, it will provide high-quality, affordable housing in an area

where housing diversity is *desperately* needed. We anticipate offering this home at less than 1/3 the cost of new construction in the neighborhood. The smaller scale is consistent with the Traditional Neighborhoods Character Area in the Comprehensive Plan, which encourages walkability with very close proximity to The Path and public transportation. We are only asking to reduce sidewalk and landscape strip requirements, not remove them. This will in no way diminish the neighborhood character but will instead make development feasible and weave into the fabric of the community unlike anything Scottdale has seen in over 100 years. Our mission is to provide the people with new housing options they can actually afford, a welcomed alternative from the million dollar new construction options which are currently being built in Scottdale. This is only possible with your help and the requested relief.

#### 4. Ordinance Hardship

A literal interpretation of Section 27-3.36.10 would prohibit any reasonable development of these lots, effectively rendering them unusable as they have sat from the time they were platted until present day. Codes and requirements have only become more constrictive to smaller homes over the years. Without relief, the lot would remain vacant and unproductive. This constitutes an undue and unnecessary hardship that was not self-created, as the lot sizes, shapes, and separation predate the current ordinance.

#### 5. Alignment with the Spirit of the Law & Comprehensive Plan Findings

The requested variances are consistent with the spirit and intent of the DeKalb County Zoning Ordinance and the **DeKalb 2050 Comprehensive Land Use Plan**. Specifically:

- **Housing Diversity and Affordability**: The Plan identifies the need for smaller, more affordable housing options to meet the needs of a broad range of residents. These homes directly advance that goal.
- Traditional Neighborhood Character: The Plan highlights the importance of walkable, traditional neighborhoods with smaller lots and houses closer to the street. The proposed variances allow us to maintain this character while adapting older lots for modern use.
- **Infill Development**: The Plan encourages efficient use of land through infill development on existing lots of record. Our proposal reactivates underutilized parcels without requiring new infrastructure.
- Sustainability and Transportation: By providing a modest-sized home, the project supports compact development patterns and aligns with County goals to reduce sprawl and encourage transit and pedestrian use.

#### Conclusion

We believe that people should not be forced to live outside of our community due to unaffordability and they should be given the opportunity to own their little slice of the

American Dream. For the reasons stated above, we respectfully request that the Board grant the requested variances from Section 27-3.36.10. We have met with DeKalb County planning officials on multiple occasions to thoughtfully craft the most ideal scenario that would most adhere to codes and achieve feasibility. The proposed relief represents the minimum deviation necessary to enable development of this unusually small lot, while protecting public welfare, furthering the goals of the Comprehensive Plan, and providing much-needed affordable housing in Scottdale. Approvals such as these by this Commission would free up many un-buildable lots in Scottdale and allow the County to fully utilize the land we have available.

Respectfully,

**Neal Hightower** 

The field data upon which this plat is based has a closure precision of one foot in 15,000+ feet and an angular error of 03" seconds per angle point and was adjusted using the Compass Rule. This plat has been calculated for closure and is found to be accurate within one foot in 100,000+ feet.

Equipment used: Topcon GTS-213 Total Station.

### FLOOD HAZARD STATEMENT:

THIS PROPERTY IS NOT IN A 100 YEAR FLOOD ZONE AS PER THE FIRM FLOOD HAZARD MAP FOR DEKALB COUNTY, GEORGIA, COMMUNIT PANEL NUMBER 13089C 0067 K, DATED 08/15/19


#### **ZONING INFORMATION:**


CLASSIFICATION: SCOTTDALE OVERLAY TIER II SETBACKS: FRONT - 30 FEET SIDE - 7.5 FEET REAR - 30 FEET MINIMUM OFFSTREET PARKING - 2 SPACES MINIMUM LOT SIZE - 5000 sf. MINIMUM LOT WIDTH - 50 FEET MINIMUM HOUSE SIZE - 1000 sf. MAXIMUM BUILDING HEIGHT - 32 FEET MAXIMUM LOT COVERAGE - 35% LANDSCAPE STRIP - 5 FEET MIN. SIDEWALK - MINIMUM 4 FEET FROM CURB

FRONT YARD TREES - 3.5" TREE EVERY 30 FEET MIN. LEGEND IPF = 1/2" REBAR FOUND IPS = 1/2" REBAR PIN SET L.L. = LAND LOTL.L.L. = LAND LOT LINE P.L. = PROPERTY LINE CL = CENTERLINEB.L. = BUILDING LINE R/W = RIGHT-OF-WAYS.S.E. = SANITARY SEWER EASEMENT D.E. = DRAINAGE EASEMENT MH = MANHOLEC.B. = CATCH BASINJ.B. = JUNCTION BOX HW = HEADWALLD.I. = DROP INLET PP = POWER/UTILITY POLE F.H. = FIRE HYDRANTI.E. = INVERT ELEVATION F.F.E. = FINISHED FLOOR ELEVATION F.F.B. = FINISHED FLOOR BASEMENT F.F.G. = FINISHED FLOOR GARAGE BOC = BACK OF CURB EP = EDGE OF PAVEMENTN/F = NOW OR FORMERLYP.O.B. = POINT OF BEGINNING ---SS--- = SANITARY SEWER LINE/PIPE -X-X-X- = FENCE LINE——— = FLOOD HAZARD ZONE LINE ——— = STORM SEWER LINE/PIPE ---W--- = WATER LINE G- = GAS LINE FW = FLOW WELL C.E. = CONSTRUCTION EASEMENT WV = WATER VALVE LS = LIGHT STANDARD WD = WOOD DECK CO = CLEAN OUT ICV = IRRIGATION CONTROL VALVE

## LOT AREA: 2582 sf. 0.059 ACRES

AREA DOES NOT INCLUDE AREA TO BE DEDICATED FOR SIDEWALK INSTALLATION






## 24 HR CONTACT: **NEAL HIGHTOWER**

614 VALLEY BROOK DRIVE SCOTTDALE, GA. 30079 (404)985-6454 NEALHIGHTOWER@GMAIL.COM

### **OWNER:**

SCOTTDALE 30, LLC 2221D PEACHTREE ROAD SUITE 220 ATLANTA, GA. 30309 (404)872-1031 JWMANGHAM@GMAIL.COM





ALPHA LAND SERVICES	
P.O. BOX 1651	
LOGANVILLE,GA. 30052	
CONTACT: ROBERT RICHARDSON	
FF: 770.696.4054 EMAIL: ROBERT@ALPHASURVEYOR.COM	
REVISION:	LAN
	DIS.


PAGE I OF 4 EXISTING CONDITIONS FOR: 436 BOOKER AVENUE

FIELD DATE: 12/24/24 AREA = 0.059 ACR PLAT DATE: 09/25/25 JOB No. 25477EX

AREA = 0.059 ACRES

TAX PARCEL #18-047-23-029 LOT: 45/46 BLOCK: \_\_\_ SUB: MEADOW BROOK ND LOT: STRICT: DEKALB \_\_\_ COUNTY

GEORGIA



INSTALLATION SPECIFICATIONS:

- INSTALLATION, PRODUCT SELECTION, AND MAINTENANCE SHALL BE IN
  ACCORDANCE WITH THE GSWCC MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA
- LOOSEN COMPACTED SOIL TO A MINIMUM DEPTH OF THREE (3) INCHES
- PRIOR TO APPLICATION.
  DRY STRAW OR HAY SHALL BE IN CLEAN CONDITION AND APPLIED BY
- HAND OR MACHINE TO A THICKNESS OF TWO (2) TO FOUR (2) INCHES. STRAW OR HAY MULCH SHALL BE ANCHORED IMMEDIATELY AFTER APPLICATION.
- MULCH ON SLOPES GREATER THAN 3% SHOULD BE ANCHORED WITH
- EMULSIFIED ASPHALT OR OTHER SUITABLE TACKIFIER.
  ADDITIONAL MULCHING IS REQUIRED IF THE MINIMUM THICKNESS IS NOT ACHIEVED OR IF SOIL COVERAGE IS LESS THAN 90%.

Ds1

DISTURBED AREA STABILIZATION WITH MULCHING

- INSTALLATION, SEED SELECTION, AND MAINTENANCE SHALL BE IN ACCORDANCE WITH THE GSWCC MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA.
- CONTROL IN GEORGIA.

  ADDITIONAL EROSION CONTROL MEASURES MAY BE NECESSARY TO ALLOW PROPER GERMINATION AND STABILIZATION.

  SOIL SURFACES MAY NEED TO BE TILLED, PITTED, OR OTHERWISE SCARIFIED TO ALLOW FOR PROPER SEED LODGING AND GERMINATION.
- APPLY LIME AT A RATE OF ONE TON PER ACRE AS NEEDED.
  APPLY 10-10-10 FERTILIZER TO SOILS WITH LOW FERTILITY AT A RATE
- OF 500 TO 700 POUNDS PER ACRE. SEEDS SHALL BE PLANTED AT A DEPTH OF TEN TIMES THE SEED
- ACCEPTABLE PLANTING METHODS INCLUDE HYDRO-SEEDING, DRILLING, AND BROADCAST SPREADING BY MACHINE OR HAND.

	PLANTING RATES		TY	PIC	AL	FI	.4.14	Tir	MG.	МС	W7	НS	
SPECIES	PER ACRE*	J	F	M	Д	М	J	ul	А	S	O	N	D
BARLEY"	144 LBS								ж	ж	×	ж	Ж
ANNUAL LESPEDEZA	40 L85	Ж	Ж	ж	ж								
WEEPING LOVEGRASS	4 LBS		×	æ	×	ж	æ						
BROWNTOP MILLET	40 LBS				ж	ж	æ	ж					
OATS	128 LBS									ж	×	ж	
RYE	168 LBS								ж	Ж.	X	ж	ж
ANNUAL RYEGRASS	40 L8S	Ж	ж	×					х	ж	ж	ж	Х
SUDANGRASS	60 LBS			×	ж	ж	×	ж	ж				
WHEAT	180 L8S									ж	x	X	×

PLANTING RATES SHOWN ARE FOR BROADCAST APPLICATIONS. REDUCE

Ds2

DISTURBED AREA STABILIZATION WITH TEMPORARY SEEDING

### MATERIALS

- Sod selected should be certified. Sod grown in the general area of the project is desirable. Sod should be machine cut and contain
- 3/4" (+ or 1/4") of soil, not including shoots or
- ±5%. Torn or uneven pads should be rejected. Sod should be cut and installed within 36 hours
- Avoid planting when subject to frost heave or hot weather, if irrigation is not available.
- The sod type should be shown on the plans or installed according to Table 2. See page 60 for your Resource Area.

Table 2. Sod Planting Requirements								
Grass	Varieties	Resource Area	Growing Season					
Bermudagrass	Common Tifway Tifgreen Tiflawn	M-L, P,C P,C P,C P,C	Warm weather					
Bahlagrass	Pensacola	P,C	Warm weather					
Centipede	Aliberta Mariano.	P,C	Warm weather					
St. Augustine	Common Bitterblue Raleigh	<sup>^</sup> C	Warm weather					
Zoysia	Zoysia Emerald P,C		Warm weather					
Tall Fescue	Kentucky 31	M-L, P	Cool weather					

- MAINTENANCE
- is not obtained. New sod should be mowed sparingly. Grass height should not be cut less than 2"-3" or as

Re-sod areas where an adequate stand of soc

Apply one ton of agricultural lime as indicated

of trash, woody debris, stones and clods larger than 1". Apply sod to soil surfaces only and not frozen surfaces, or gravel type soils.

Bring soil surface to final grade. Clear surface

- Topsoil properly applied will help guarantee a stand. Don't use topsoil recently treated with herbicides or soil sterilants.
- Mix fertilizer into soil surface. Fertilize based on soil tests or Table 1. For fall planting of warm season species, half the fertilizer should be applied at planting and the other half in the
- Sod should be cut to the desired size within . Agricultural lime should be applied based on soil tests or at a rate of 1-2 tons/acre.
  - Lay sod with tight joints and in straight lines. Don't overlap joints. Stagger joints and do not

Table 1. Fertilizer Requirements for Soil Surface Application

Fertilizer Type (lbs./acre)	Fertilizer Rate (lbs./sq.ft.)	Fertilizer Rate	Season
10-10-10	1000	.025	Fall

- · On slopes steeper than 3:1, sod should be anchored with pins or other approved methods.
- · Installed sod should be rolled or tamped to provide good contact between sod and soil.
- · Irrigate sod and soil to a depth of 4" immediately after installation
- · Sod should not be cut or spread in extremely wet or dry weather.
- · Irrigation should be used to supplement rainfall for a minimum of 2-3 weeks.
- Fertilize grasses in accordance with soil tests or Table 3.


Types of Species	Planting Year	Fertilizer (N-P-K)	Rate (lbs./acre)	Nitroger Top Dressin Rate (lbs./acr)
Cool	First	6-12-12	1500	50-100
season	Second	6-12-12	1000	
grasses	Maintenance	10-10-10	400	30
Warm	First	6-12-12	1500	50-100
	Second	6-12-12	800	50-100

#### MAINTENANCE

The exit shall be maintained in a condition which will prevent tracking or flow of mud onto public rights-of-way. This may require periodic top dressing with 1.5-3.5 inch stone, as conditions demand, and repair and/or cleanout of any structures to trap sediment. All materials spilled,

dropped, washed, or tracked from vehicles or site onto roadways or into storm drains must be

### CRUSHED STONE CONSTRUCTION EXIT



- NOTES:
  1. AVCID LOCATING ON STEEP SLOPES OR AT CURVES ON PUBLIC ROADS.
  2. REMOVE ALL VEGETATION AND OTHER UNSLITABLE MATERIAL FROM THE FOUNDATION AREA, GRADE, AND CROWN FOR POSITIVE DRAINAGE.
- CROWN FOR POSITIVE DRAINAGE.

  3. AGGREGATE SIZE SHALL BE IN ACCORDANCE WITH NATIONAL STONE ASSOCIATION R-2 (1.5"-3.5" STONE).

  4. GRAVEL PAD SHALL HAVE A MINIMUM THICKNESS OF 6".

  5. PAD WIDTH SHALL BE EQUAL FULL WIDTH AT ALL POINTS OF VEHICULAR EGRESS, BUT NO LESS THAN 20'.

  6. A DIVERSION RIDGE SHOULD BE CONSTRUCTED WHEN GRADE TOWARD PAVED AREA IS GREATER THAN 2X'.

  7. INSTALL PIPE UNDER THE ENTRANCE IF NEEDED TO NAINTAIN DRAINAGE DITCHES.

  8. WHEN WASHING IS REQUIRED, IT SHOULD BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT
- OWNER WASHING IS REQUIRED, IT SHOULD BE DONE OF AN ARRA STABILIZED WITH CRUSTAGE STORE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN (DIOPERT ALL SURFACE RUNOFF AND DRAINAGE FROM THE ENTRANCE TO A SEDIMENT CONTROL DEVICE).

  9. WASHRACKS AND/OR THE WASHERS MAY BE REQUIRED DEPENDING ON SCALE AND CIRCUMSTANCE. IF NECESSARY, WASHRACK DESIGN MAY CONSIST OF ANY MATERIAL <u>SUITABLE</u> FOR TRUCK TRAFFIC THAT REMOVE MUD AND DIRT.
- 10. MAINTAIN AREA IN A WAY THAT PREVENTS TRACKING AND/OR FLOW OF MUD ONTO PUBLIC
- RIGHTS-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEANOUT OF ANY MEASURES. USED TO TRAP SEDIMENT.

Figure 6-14.1

GSWOC (Armended - 2013)

6-142

- INSTALLATION, SEED SELECTION, AND MAINTENANCE SHALL BE IN ACCORDANCE WITH THE GSWCC MANUAL FOR EROSION AND SEDIMENT
- PERMANENT VEGETATION SHALL INCLUDE GROUND PREPARATION, LIMING, FERTILIZING, SEEDING, AND MULCHING.
- INTERIM EROSION CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL AT LEAST 70% OF THE EXPOSED SURFACE IS SUFFICIENTLY STABILIZED. PREPARE THE LAND FOR SEEDING BY APPLYING LIME AND FERTILIZER AND DISKING THE SURFACE TO A MAXIMUM DEPTH OF FOUR (4) INCHES.
- FINISHED SURFACE SHALL BE SMOOTH, UNIFORM, AND FREE OF DEBRIS SUCH AS TRASH, ROCKS, ROOTS, AND WEEDS. MULCH SHALL BE APPLIED UNIFORMLY WITHIN 24 HOURS OF SEEDING. REFER TO THE MANUAL FOR EROSION AND SEDIMENT CONTROL IN

VEGETATIVE COVER SUCH AS TREES AND SHRUBS.

GEORGIA FOR ADDITIONAL PLANTING SPECIFICATIONS AND ALTERNATIVE

		·····	***************************************										
SPECIES	PLANTING RATES PER ACRE*	ij.	F	M	AL A	M	JAN	J	А	S	0	N	D
BAHIA	60 LBS	ж	х	×	Ж	ж	Х	ж	Ж	х	х	,b(	ж
BERMUDA (HULLED)	TO LBS		х	ж	х	Х	х						
BERMUDA (UNHULLED)	10 LBS	ж	х								Х	х	ж
TALL FESCUE	50 LBS			ж	х				ж	х	х	ж	
WEEPING LOVEGRASS	4 LBS			ж	ж	ж	Х						
SERICEA LESPEDEZA	60 LBS		Х	X	ж	Х	Х						

\* PLANTING RATES SHOWN ARE FOR BROADCAST APPLICATIONS. REDUCE THESE RATES BY 50% FOR SEED DRILLING.

LIME AND FERTILIZER APPLICATION: GRADED AREAS REQUIRE LIME APPLICATION.


AGRICULTURAL LIME SHALL BE APPLIED AT A RATE OF ONE (1) TO TWO (2) TONS PER ACRE UNLESS SOIL TESTS SUGGEST OTHERWISE. REPEAT APPLICATION EVERY FIVE (5) YEARS OR AS NEEDED.


TYPE OF SPECIES	PLANTING YEAR	RECOMMENDED N-P-K	FERTILIZER RATE PER ACRE
	##	6-12-12	1500 LBS
COOL SEASON GRASSES	2 <sup>2</sup> 3	6-12-12	1000 LBS
700 17 5.5. 17 1000 1000 1000 1000 1000 1000 1000	MAINTENANCE	10-10-10	400 LBS
COOL SEASON	1	6-12-12	1500 LBS
GRASSES AND	2	0-12-12	1000 LBS
LEGUMES	MAINTENANCE	0-10-10	400 LBS
	1	6-12-12	1500 LBS
WARM SEASON GRASSES	2	6-12-12	800 LBS
W	MAINTENANCE	10-10-10	400 LBS
WARM SEASON	#	6-12-12	1500 LBS
GRASSES AND	2	0-10-10	1000 LBS
LEGUMES	MAINTENANCE	0-10-10	400 LBS

\* PERMANENT SEEDING MAY BE SUBSTITUTED WITH SODDING (Ds4) AT THE DISCRETION OF THE PROPERTY OWNER AND LOCAL INSPECTOR.

DISTURBED AREA STABILIZATION Ds3WITH PERMANENT SEEDING

### SILT FENCE Sd1-S (TYPE C)





1. USE STEEL OR WOOD POSTS OR AS SPECIFIED BY THE EROSION, SEDIMENTATION,

HEIGHT (\*) IS TO BE SHOWN ON THE EROSION, SEDIMENTATION, AND POLLUTION CONTROL PLAN.

GSWCC 2016 Edition

Figure 6-27.2

# STRAW BALES DETAIL NOTE 1. STAKES SHALL BE WOOD AND SHALL BE 2" x 2" NOMINAL. 2. EROSION BALES SHALL BE 18" × 18" × 36". 3. EROSION BALES SHALL BE ENTRENCHED 4 IN. MINIMUM INTO THE SOIL, THIGHTLY ABUTTED WITH NO CAPS, STAKED, AND BACKFILLED AROUND THE ENTIRE OUTSIDE PERIMETER. Wood stake (TYP.) Step 1: excavate the trench Twine or wire Wood stake (TYP.) Wedge loose certified weed free straw osion bale trenching between erosion bales tep 2: Place and stake the ension bales

GSWCC GEORGIA SOIL AND WATER CONSERVATION COMMISSION ROBERT W. RICHARDSON LEVEL II CERTIFIED DESIGN PROFESS CERTIFICATION NUMBER 000008932 SSUED: 10/11/2019 EXPIRES 10/11 09/25/25 SIGNATURE DATE ALPHA LAND SERVICES P.O. BOX 1651 LOGANVILLE, GA. 30052

REVISION:

REF. PLAT: PB.


NOTES & DETAILS FOR: 436 BOOKER AVENUE


PLAT DATE: 09/25/25 JOB No. 25477S2


PAGE 3 OF 4


CONTACT: ROBERT RICHARDSON TAX PARCEL #18-047-23-029 OFF: 770.696.4054 EMAIL: ROBERT@ALPHASURVEYOR.COM LOT: 45/46 BLOCK: SUB: MEADOW BROOK LAND LOT: DISTRICT: DEKALB GEORGIA FIELD DATE: 12/24/24 AREA = 0.059 ACRES

6-142










1.) DOWN DRAINS SHALL HAVE POSITIVE SLOPE AWAY FROM FOUNDATION.



TOP & SIDES OF PIT TO—
BE LINED WITH NON—WOVEN
FILTER FABRIC

∠3 – 8 FEET OF STON
40% VOID STORAGE
PRE-WASHED

GRAVEL TRENCH : N.T.S.

2.) DOWN SPOUTS SHALL NOT BE DISCHARGE CLOSER THAN 5' FROM FOUNDATION

INFILTRATION TRENCH MAINTENANCE ACTIVITIES AND SCHEDULE	
ACTIVITY	SCHEDULE
- REPLACE GRAVEL AND TOPSOIL (WHEN CLOGGED)	AS NEEDED
<ul> <li>CLEAR INLETS OF DEBRIS, INCLUDING SEDIMENT AND OIL/GREASE</li> <li>STABILIZE THE SURROUND AREA.</li> <li>MOW GRASS AND REMOVE GRASS CLIPPINGS FROM FILTER STRIP AREAS, IF APPLICABLE</li> <li>REPAIR UNDERCUT AND ERODED AREAS AT INFLOW/OUTFLOW STRUCTURES.</li> </ul>	MONTHLY
<ul> <li>INSPECT PRETREATMENT DEVICES AND DIVERSION STRUCTURES FOR DEBRIS ACCUMULATION AND STRUCTURAL INTEGRITY; TAKE CORRECTIVE ACTION AS NEEDED.</li> </ul>	SEMIANNUALLY
- AERATE PRETREATMENT BASIN BOTTOM OR DE- THATCH BASIN BOTTOM, IF APPLICABLE.	ANNUALLY
SCRAPE PRETREATMENT BASIN BOTTOM TO     REMOVE ACCUMULATED SEDIMENT AND RE—SEED     GROUND COVER, IF APPLICABLE.	EVERY 5 YEARS
TOTALLY REHABILLITATE THE TRENCH AND RESTORE ITS DESIGN STORAGE CAPACITY.	UPON FAILURE
- EXCAVATE TRENCH WALLS TO EXPOSE CLEAN SOIL IF APPLICABLE.	

GSWCC GEORGIA SOIL AND WATER CONSERVATION COMMISSION

ROBERT W. RICHARDSON

LEVEL II CERTIFIED DESIGN PROFESSIONAL

CERTIFICATION NUMBER 0000089322

ISSUED: 10 11/2019 EXPIRES 10/11

09/25/25

SIGNATURE DATE

PAGE 4 OF 4 NOTES & DETAILS FOR: ALPHA LAND SERVICES P.O. BOX 1651 LOGANVILLE,GA. 30052 436 BOOKER AVENUE CONTACT: ROBERT RICHARDSON TAX PARCEL #18-047-23-029 OFF: 770.696.4054 EMAIL: ROBERT®ALPHASURVEYOR.COM LOT: 45/46 BLOCK: SUB: MEADOW BROOK LAND LOT: ... DISTRICT: \_\_\_ **REVISION:** DEKALB \_\_\_\_ COUNTY GEORGIA FIELD DATE: 12/24/24 AREA = 0.059 ACRES
PLAT DATE: 09/25/25 JOB No. 25477S3 REF. PLAT: PB.