

Attachment N - Tank Locations

Please Note: That Due To The Current Covid-19 Pandemic CDC Guidelines Will Be Adhered To. A Well-Fitted Facial Mask That Covers The Nose And Mouth Are Required At All Times During The Site Visit. The Practice Of Social Or Physical Distancing (6 Feet Apart Of Each Other) Will Be Required At All Times During The Site Visit. If You Are Experiencing A Fever, Flu-Like Symptoms Or General Malaise, Please Do Not Attend. Only Two (2) Representatives From Each Company Shall Attend, Hard Hats Are Required. Bidders or its authorized representative shall sign in with a representative of DeKalb County's Purchasing and Contracting department at the site visit as proof of attendance.

Continued on next page

Attachment N - Tank Locations Day 1

Monday October 19, 2021

1. **Dunwoody #1 - Ground Storage Tank- 5335 Roberts Road, Dunwoody, GA 30338**
Installation required: Mount in Existing PLC Enclosure 1 Materials (Unistrut, Conduit, Wires, and etc.)

PLC and HMI Amendments required: Add Analog Input Card 1 A-B MicroLogix 4 pt. AI Module, 4-20 mA or 1-5 VDC, #1762-IF4
2. **Dunwoody #2 - Elevated Tank- 4993 Ashford-Dunwoody Rd, Dunwoody, GA 30338**
Installation required: Mount inside customer provided and installed Fiberglass Enclosure 1 Materials (Unistrut, Conduit, Wires, and etc.)

PLC and HMI Amendments required: Add Analog Input Card 1 A-B MicroLogix 4 pt. AI Module, 4-20 mA or 1-5 VDC, #1762-IF4
3. **Tucker #1 - Ground Storage Tank – 4226 Lawrenceville Hwy, Tucker, GA 30084**
Installation required: Mount in Existing PLC Enclosure 1 Materials (Unistrut, Conduit, Wires, and etc.)

PLC and HMI Amendments required: Add Analog Input Card 1 A-B MicroLogix 4 pt. AI Module, 4-20 mA or 1-5 VDC, #1762-IF4
4. **Tucker #2 - Elevated Tank – 1750 Stoneridge Drive, Stone Mountain, GA 30083**
Installation required: Mount on Unistrut Stand next to existing PLC 1 Materials (Unistrut, Conduit, Wires, and etc.)

PLC and HMI Amendments required: Add Analog Input Card 1 A-B MicroLogix 4 pt. AI Module, 4-20 mA or 1-5 VDC, #1762-IF4
5. **Clairmont - Elevated Tank- 1901 Mason Mill Rd, Decatur, GA 30033**
Installation required: Mount inside customer provided and installed Fiberglass Enclosure 1 Materials (Unistrut, Conduit, Wires, and etc.)
6. **Avondale - Ground Storage Tank - 3252 Covington Hwy, Decatur, GA 30032**
Installation required: Mount inside customer provided and installed Fiberglass Enclosure 1 Materials (Unistrut, Conduit, Wires, and etc.)

Attachment N - Tank Locations Day 2

Tuesday October 20, 2021

- 7. Redan #1 and #2 - Ground Storage Tanks – 1300 Panola Road, Stone Mountain, GA 30088**
Installation required: Mount in same room as existing PLC 1 Materials (Unistrut, Conduit, Wires, and etc.)

PLC and HMI Amendments required: Add Analog Input Card 1 A-B MicroLogix 4 pt. AI Module, 4-20 mA or 1-5 VDC, #1762-IF4
- 8. Lithonia - Ground Storage Tank – 6670 Parkway Drive, Lithonia, GA 30058**
Installation required: Mount to wall perpendicular to existing PLC Panel 1 Materials (Unistrut, Conduit, Wires, and etc.)
- 9. Wesley Chapel #1 and #2 - Ground Storage Tanks- 3337 Wesley Chapel Road, Decatur GA 30032**
Installation required: Mount to wall behind existing PLC Panel 1 Materials (Unistrut, Conduit, Wires, and etc.)

PLC and HMI Amendments required: Add Analog Input Card 1 A-B MicroLogix 4 pt. AI Module, 4-20 mA or 1-5 VDC, #1762-IF4
- 10. Whites Mill #1 and #2 - Ground Storage Tanks - 2346 Jenay Ct. , Decatur, GA 30032**
Installation required: Mount to wall beside existing PLC Panel 1 Materials (Unistrut, Conduit, Wires, and etc.)

PLC and HMI Amendments required: Add Analog Input Card 1 A-B MicroLogix 4 pt. AI Module, 4-20 mA or 1-5 VDC, #1762-IF4
- 11. McAfee - Elevated Tank – 2532 McAfee Road, Decatur, GA 30032**
Installation required: Mount inside customer provided and installed Fiberglass Enclosure 1 Materials (Unistrut, Conduit, Wires, and etc.)

PLC and HMI Amendments required: Replace existing Siemens PLC with Allen Bradley MicroLogix 1400 plus Analog Input Card 1 A-B MicroLogix 1400 CPU #1766-L32BWAA 1 Ethernet Port, 2 Serial Ports, 20 DI, 12 DO, 4 AI, 2 AO, 120 VAC 1 A-B MicroLogix 4 pt. AI Module, 4-20 mA or 1-5 VDC, #1762-IF4
- 12. Columbia #1 and #2 - Ground Storage Tanks - 1742 Columbia Drive, Decatur, GA 30032**
Installation required: Mount to wall adjacent to existing PLC Panel 1 Materials (Unistrut, Conduit, Wires, and etc.)