

Table 2 - Total Estimated Excavation Volumes (Disposal and Handling)

Excavation	Depth Interval	Type	Square Footage	Est. Cu. Yds.	Est. Tons ^
Remedial Area 1	0-5 ft	Potential Hazardous	1,150	213	319
Remedial Area 2	0-8 ft	Potential Hazardous	700	207	311
Total Soil Work Movement:				420	631

Notes:

^, Using a **1.50 tons/cu.yd.** multiplier.

1 - Assuming potentially hazardous soils are rendered non-hazardous through resample/ treatment

Assumes vertical excavation sidewalls with no setbacks.