

(Revised July 5, 2021)  
**ATTACHMENT B**

**BIDDER'S UNIT PRICE FORM**

**\*\*\*NEW-BID PRICE FORM MUST BE SUBMITTED IN A SEPARATE SEALED ENVELOPE OR BIDDER WILL BE DEEMED NON-RESPONSIVE AND WILL NOT BE CONSIDERED FOR AWARD\*\*\***

TO: The Governing Authority of DeKalb County, Georgia

The undersigned, as Bidder, declares that he has carefully examined ITB No. 21-101333, Reindeer Drive Water Main Replacement (Multiyear Contract), an annexed proposed form of Contract, the Specifications therein contained, and the Drawings therein referred to, and that he proposes and agrees that if his Bid is accepted, to provide the necessary machinery, tools, apparatus, and other means of construction, and will furnish all materials and labor specified in the Contract, or called for by the Drawings, or necessary to complete the Work in the manner therein specified within the time specified, as therein set forth for the unit prices on the form following this page.

By signature hereon, the Bidder's authorized agent ("Agent") certifies that all necessary corporate acts have been taken to authorize the Agent to sign this document and that all information provided in Bidder's Unit Price Form is an accurate representation of the information the Bidder's is providing.

Bidder's Name: \_\_\_\_\_

Signature of Agent: \_\_\_\_\_

Printed Name: \_\_\_\_\_

Title: \_\_\_\_\_

Date: \_\_\_\_\_

(Revised July 5, 2021)

**ATTACHMENT B-1 BIDDER'S UNIT PRICE FORM**

BID ITEM	DESCRIPTION	UNIT	QTY	UNIT PRICE	EXTENDED AMOUNT
1	MOBILIZATION AND DEMOBILIZATION	LS	1	\$	\$
2	MAINTENANCE OF TRAFFIC	LS	1	\$	\$
3	NPDES MONITORING AND REPORTING	LS	1	\$	\$
4	ORANGE BARRIER FENCE (Tr)	LF	1,000	\$	\$
5	CONSTRUCTION EXIT (Co)	EA	2	\$	\$
6A	SILT FENCE – TYPE S (Sd1-S)	LF	500	\$	\$
6B	SILT FENCE – TYPE NS (Sd1-NS)	LF	2,100	\$	\$
7	ROCK FILTER DAM (Rd)	EA	5	\$	\$
8A	STONE RIPRAP TYPE I, 24" IN PLACE	CY	110	\$	\$
8B	STONE RIPRAP TYPE III, 12" IN PLACE	CY	210	\$	\$
9	STRAW BALES (Cd-Hb)	EA	50	\$	\$
10	INLET SEDIMENT TRAP (Sd2-P)	EA	15	\$	\$
11	COMPOST SOCKS FOR CHECK DAM (Cd-Fs)	EA	50	\$	\$
12	ROLLED EROSION CONTROL BLANKET AND MATTING (RECP)	SY	100	\$	\$
13A	MULCHING - DISTURBED AREA STABILIZATION (Ds-1)	SY	4,000	\$	\$
13B	PERMANENT SEEDING / VEGETATION - DISTURBED AREA STABILIZATION (Ds-3)	SY	3,000	\$	\$
14	SOD - FINAL STABILIZATION (Ds-4), WHERE DIRECTED BY OWNER	SY	1,000	\$	\$
15	SIDEWALK RESTORATION	SY	1,000	\$	\$
16	COMBINATION CURB AND GUTTER RESTORATION	LF	400	\$	\$
17	GRANITE CURB REMOVAL AND REPLACEMENT	LF	300	\$	\$
18	FREE BORE	LF	3,600	\$	\$

Addendum No. 4  
ITB 21-101333  
Reindeer Drive Water Main Replacement (Multiyear Contract)

19A	ROADWAY RESTORATION - 1 1/2" MILL AND 1 1/2" ASPHALT TOP OVERLAY	SY	17,000	\$	\$
19B	ROADWAY RESTORATION - 1 1/2" ASPHALT TOP	SY	17,000	\$	\$
19C	ROADWAY RESTORATION - 4" BINDER	SY	17,000	\$	\$
19D	ROADWAY RESTORATION - 10" GAB	SY	9,700	\$	\$
19E	ROADWAY RESTORATION - 8" CONCRETE BASE	SY	9,700	\$	\$
20	PAINTING TRAFFIC STRIPE / ARROWS / MARKINGS	LS	1.00	\$	\$
21A	1.5" COPPER TUBING TYPE K, INCLUDES FITTINGS	LF	350	\$	\$
21B	8" DUCTILE IRON PIPE (DIP), INCLUDES FITTINGS AND THRUST BLOCKS / COLLARS - CLASS 350	LF	14,500	\$	\$
21C	8" RESTRAINED JOINT (RJ) DIP, INCLUDES FITTINGS AND THRUST BLOCKS / COLLARS - CLASS 350	LF	3,800	\$	\$
21D	16" DUCTILE IRON PIPE (DIP), INCLUDES FITTINGS AND THRUST BLOCKS / COLLARS - CLASS 350	LF	3,150	\$	\$
21E	16" RESTRAINED JOINT (RJ) DIP, INCLUDES FITTINGS AND THRUST BLOCKS / COLLARS - CLASS 350	LF	450	\$	\$
22B	TAPPING SLEEVE & VALVE ASSEMBLY 8" X 8"	EA	4	\$	\$
22E	TAPPING SLEEVE & VALVE ASSEMBLY 8" X 6"	EA	2	\$	\$
22F	TAPPING SLEEVE & VALVE ASSEMBLY 16" X 16"	EA	2	\$	\$
23	GROUT-FILL EXISTING WATERLINE (ALL SIZES)	CY	400	\$	\$
24	CUT AND PLUG EXISTING WATER MAIN	EA	4	\$	\$
25A	JACK AND BORE - 8" CARRIER PIPE IN 18" STEEL CASING	LF	550	\$	\$
25B	JACK AND BORE - 16" CARRIER PIPE IN 30" STEEL CASING	LF	550	\$	\$
26	8-MIL POLYETHYLENE SLEEVE FOR 8" AND 16" DIP	LF	650	\$	\$
27	CONNECTION TO EXISTING WATER MAIN	EA	6	\$	\$
28A	FURNISH AND INSTALL 8" GATE VALVE WITH VALVE BOX AND EXTENSION	EA	65	\$	\$

Addendum No. 4  
 ITB 21-101333  
 Reindeer Drive Water Main Replacement (Multiyear Contract)

28B	FURNISH AND INSTALL 16" GATE VALVE WITH VALVE BOX AND EXTENSION	EA	5	\$	\$
29	RELOCATE EXISTING FIRE HYDRANT ASSEMBLY AND VALVE	EA	5	\$	\$
30	NEW FIRE HYDRANT ASSEMBLY	EA	45	\$	\$
31	TRANSFER WATER SERVICE	EA	250	\$	\$
32	REPLACE EXISTING WATER METER AND METER BOX	EA	175	\$	\$
33	RELOCATION OF EXISTING WATER SERVICE	EA	100	\$	\$
34	REMOVAL OF UNSUITABLE SOIL AND REPLACEMENT WITH SUITABLE SOIL	CY	1,500	\$	\$
35	ROCK EXCAVATION AND REPLACEMENT WITH SUITABLE SOIL	CY	1,500	\$	\$
36	TESTING LABORATORY SERVICES	LS	1	\$	\$
37	TREE REMOVAL	EA	5	\$	\$
38	AIR RELEASE VALVES WITH VAULT	EA	2	\$	\$
				BASE PRICE TOTAL	
39	OWNER ALLOWANCE:				\$900,000.00

**TOTAL BID (BASE PRICE TOTAL + OWNER ALLOWANCE):**

\_\_\_\_\_ \$ \_\_\_\_\_  
 (State in words on the line above) (In figures)

**NOTE TO SUPPLIER:**

**Note 1:** The 8-inch ductile iron pipe water main from STA 500+00 to STA 1023+11 (Holly Ln NE, Bramble Rd NE, Unnamed St, Jody Ln NE, Holly Ln NE, Reindeer Dr NE, Christmas Ln NE, Pinetree Cir and Merry Ln NE) as noted on Drawings C-141 through C-159 is to be installed within the roadway, under pavement, with trench patch resurfacing required, (with the exception of Holly Ln NE from North Druid Hills Rd to Christmas Ln which must be resurfaced single full lane from approximately centerline of road to curb), instead of installation as currently shown on the bid drawings behind the curb through yards. Bid quantities have been revised to reflect this change of installation location for the 8-inch water main.

**Note 2:** Every line item must be completed to be considered for award.

These quantities are approximate and may be increased or decreased as to any and all units as necessary to complete the construction of said Project without entitling the Contractor to any claim for extra

compensation because of any injury, damage or delay he may sustain on account of such increase or decrease. The Contractor shall be entitled to compensation on the foregoing unit prices only on the quantities of materials actually furnished and work actually done as determined and approved in writing by the County through an inspection of the work completed. In no event shall the County be liable for payment in excess of the total Bid without proper prior written authorization via Change Order from the County. The Total Bid includes and encompasses the cost of all labor, materials, equipment, tools, supervision, scheduling, safety program, coordination, engineering, testing, surveys, layout, cleanup, and other things and services required to complete the entire Project in strict conformity with the Drawings, Specifications, the Contract, and all addenda and authorized written clarifications issued prior to the Bid date. Without limitation, the Total Bid also includes all applicable sales and use taxes, fees, temporary lighting, security for the site, heating and cooling, temporary utilities, freight costs, handling costs, permit costs, field and main office costs, bond premiums, insurance premiums, direct and indirect administrative costs, overhead, and profit.

Bidder has examined the site of the proposed Work and all documents comprising the Contract and is satisfied as to the conditions to be encountered in performing the work and as to the requirements of the Contract.

**No Bid may be revoked or withdrawn until ninety (90) days after the time set for opening the Bids.**